SUBARUPRIMEFOCUSSPECTROGRAPH

Updates of the next-generation Subaru facility instrument under commissioning











Naoyuki Tamura [Kavli IPMU -> Subaru/NAOJ] On behalf of PFS collaboration

Jan 31 2023 JST Subaru Users Meeting FY2022 Prime Focus Spectrograph

PFS commissioning has been underway.



Engineering First Light in Sep 2022

Successfully observed many stars simultaneously by intentionally positioning the fibers on the targets.

Wavelength (630-970nm

~600

300s exposure of stars in an NGC 1980 field w/ SM1 red camera

Now two fiber cables & two spectrograph modules in place

Cable B1 & B2

on the telescope spider

Successful installation of 2nd Fiber Cable (Cable B2) in April 2022.



- Completed installing SM3 in early Nov 2022.
- Started its operation right away according to the good results of post-installation tests.

The observation in Nov 2022 with doubled multiplicity: $\sim 600 \rightarrow \sim 1200$

Two more modules to come for the full multiplicity of ~2400

300s exposure of stars in an NGC 1980 field w/ SM1 & SM3 blue cameras



8mm between adjacent Cobras

Fiber positioning accuracy

- Accurately predict (x,y) from (α, δ) .
- Accurately move the fiber to requested (x.y). 2.



x (mm)

Raster scan

To generate a 2D map of flux coming into the instrument around each fiber.



The fiber diameter is equivalent to 100um

- 1".13@Field center
- 1".03@Field edge

Fiber positioning accuracy



Data processing



Updates are applied to the pipelines continuously.

→ <u>Weekly</u> integration test: 2D (Princeton), 1D (LAM) & <u>End-to-end (IPMU)</u>



2D Data Reduction Pipeline (2D DRP)

<u>Current status:</u>

- The pipeline (Lupton, Price+) is getting to be able to process data from engineering observations all the way down to flux calibration that is being developed at NAOJ (Yamashita, Mineo+).
- 2D PSF modeling as a key to very good sky subtraction still needs substantial development, while the spectrograph part seems quite well modeled already (Caplar, Hayashi, Yabe, 'PFI/DCB (fiber 255, angle=26.1')
- Useful QA plots are be those for accuracies of¹ calibration and sky sub appropriate tools neec (Hamano, Tanaka, Yabe,⁰ Siddiqu²⁰⁰ Price+)⁴⁰⁰





1D Data Reduction Pipeline (1D DRP)



HSC+PFS Science Database (SciDB)

- SciDB (currently ver. <u>2.5) is</u> a <u>Science Platform</u> for HSC+PFS being jointly developed by **NAOJ** and JHU which plans to:
 - Provide easy access to outputs from the PFS pipelines as well as those

SciServer (

the primary analysis environment

		803			
Files		Groups		Compute Jobs	
You have 0 Shared User Volumes.		You have 0 Group Invitations.		You have 0 Jobs Running.	
You have 2 Owned User Volumes.		You have 0 Owned Groups.		You have 0 Jobs Completed in 24 hours.	
ciServer Ap	ops				
۲			1		
Compute	Online SQL	Schema	hscMap	File Search	Image Cutouts
nalyze data with teractive Jupyter	A multi-featured	Your database	Your nagivator around the deep	Looking for flat	Get postage stamps of your
notebooks in	editor to check and	navigator	sky	files?	objects
Python.	submit queries				
PSF Picker					
ant to know PSF					
around your					





Hisanori Furusawa Michitaro Koike Sogo Mineo Takahiro Morishima Kazumi Murata Yuki Okura Masayuki Tanaka



Dmitry Medvedev Arik Mitschang Manu Taghizadeh-Popp Ani Thakar Sue Werner

Towards the end of PFS commissioning & beyond

2nd Fiber Cable (Cable B2) was installed (Apr 2022).

Engineering observations
3 runs in S23A
2 (TBC) runs in S23B
Open use readiness review
TBD runs in S24A for e.g. stabilization
Start of science operation (S24B)

2024





2022

2nd Spectrograph Module (SM3) was installed (Nov 2022).

Fiber Cable installation

- Cable B3 on 2/6-8 (next week)
- Cable B4 (TBC)

2023

- Spectrograph implementation
 - NIR camera SN1, SN2 by mid April
 - \rightarrow NIR First Light in the April run
- All the rest in June-July
 - \rightarrow 1st run w/ the full hardware in July.



Spectrograph System (SpS) at LAM

- Tests of the 1st NIR camera (N1) as part of Spectrograph Module #2 (SM2) are ongoing.
 - N1 itself was fully assembled and tested at JHU, passed the preship review and was shipped to LAM.
 - The optical alignment at LAM looks as good as how it was at JHU. The image quality and thermal background are being investigated in detail at 5°C in the chamber to simulate the operating condition at Subaru.
 - The NIR camera will be soon confirmed to be confocal to a visible camera.
 - Near-term goal is to deliver N1 to Subaru in Mar.
- The assembly & test of the remaining visible cameras are also ongoing.

Visible camera under metrology









NIR Cameras #2,#3, #4 (N2-4) at JHU

• N2:

- Image quality and thermal background have been conformed good.
- Scattered light test is underway.
- N3:
 - Image quality check is ongoing. So far so good.
 - Thermal background measurement is ongoing.
- N4:
 - The cryostat assembly is nearly done to start pumping for tests.
 - The detector characterization is ongoing in the test dewar.

• Near-term goal is to deliver N2 to Subaru in March.



Preparations for open-use observation operation

The main site of discussion and development is the Observation processing ("*Obsproc*") WG.



- Characterizing the instrument
- Maximizing observation efficiency
- Implementing required book-keeping

PFS lineup at this Users Meeting

P07 by Shintaro Koshida (Subaru)



P07: Summary of PFS Engineering Observations in FY 2

Shintaro Koshida, Yuki Moritani (Subaru Telescope/NAOJ), Naoyuki Tamura (Kavli IPMU), Robert Lupton, Craig Loomis, Arnaud Le Fur, Hassan Siddiqui (Princeton University), Chi-Hung Yan, Jennifer Karr (ASIAA), Hiroshige Yoshida, Satoshi Kawanomoto, Yuhei Takagi, Akira Arai, Eric Jeschke, Masato Onodera (Subaru Telescope/NAOJ), Kiyoto Yabe (Kavli IPMU), and PFS Collaboration



The discussion session later today by Pyo (+ Tanaka, <u>Onodera, Tak</u>agi) and Oguri

HUGE thanks to all hard TEAM WORKs

(Apologies to many people missed on the photos ...)



<u>PFS instrumentation</u> is now on the home stretch.

- Engineering observations
 - Engineering First Light in Sep 2022
 - Fiber positioning accuracy is getting better.
 - Minimizing the systematic errors that dominate the accuracy is next priority.

Ongoing hardware development

SM2 is being tested at LAM with the NIR camera. 3 other NIR cameras are being tested at JHU.

Timeline

- Installing Cable B3/B4 on the telescope next week/late Mar.
 - Aiming to install 1-2 NIR cameras by mid April, and the rest of SpS in June-July.
 - NIR first light in the April run.
 - 1st run with the full hardware in July.
- Open-use readiness review in Jan 2024 for science operation from S24B.











- ✓ Official web site <u>https://pfs.ipmu.jp/</u>
- Membership registration <u>https://pfs.ipmu.jp/research/regist_collab.html</u>
- ✓ Blog <u>https://pfs.ipmu.jp/blog/</u>
- ✓ Instagram <u>https://www.instagram.com/pfs_collaboration/</u>