

SWIMS

A New NIR MOS Spectrograph for TAO 6.5m Telescope

K. Motohara, M. Konishi, K. Tateuchi, N. Mitani, T. Aoki, K. Asano,
M. Doi, T. Handa, K. Kawara, K. Kohno, S. Koshida, T. Minezaki,
T. Miyata, T. Nakamura, S. Sako, T. Soyano, M. Tanaka, T. Tanabe,
K. Tarusawa, and Y. Yoshii






TAO

The University of Tokyo Atacama Observatory Project


- * Construct an infrared-optimized 6.5m telescope at the world's highest site of 5650m(18000ft) altitude, Co. Chajnantor at Atacama desert, Chile
- * Current status:
 - * Installed a 1m telescope (called miniTAO), and started observations in the near- to mid infrared





Advantage of Co. Chajnantor

- * Photometric nights > 60%, / usable >80% (Miyata+08)
- * Median Seeing 0.7'' @ V-band (KM+08)
- * High Transmittance by low pressure (<0.5atm) + dry climate \leq PWV 0.5mm (25%tile) (1mm@MKO)




**Excellent observational condition in
both NIR(1-2.5mm) and MIR (5-40mm)**



SWIMS

Simultaneous-color Wide-field Imager and Multi-object Spectrograph

- * NIR Spectrograph for TAO 6.5m
 - * **Wide-Field** (9.6' ϕ FoV on TAO)
 - * **MOS** Spectrograph
 - * **2-band simultaneous** Imaging/Spectroscopy
: 0.9-1.4 and 1.4-2.5 μ m
 - * $R \sim 1000$ (4pix/0.52" slit)
- * Funded as a part of "Economy Stimulus Budget", 2009-2010






Science with SWIMS

Galaxy Redshift Surevey

- * High transmittance at TAO site
: Ideal for the **redshift survey** in the infrared
- * Full 0.9-2.5 μm spectra can be obtained simultaneously
: **precise continuum / line ratio measurement** possible
- * Simultaneous Hi-z Narrow-band Imaging (e.g. $\text{H}\alpha/\text{OIII}$, $\text{H}\beta/\text{OII}$)






Science with SWIMS

New Window for Pa α

- * Hydrogen Pa α line (1.8751 μ m) available
 - * Strongest Hydrogen Line in NIR
 - * Good probe in dusty environment





Pa α Imaging with ANIR at Co. Chajnantor



Galactic Center (Sgr A*)


Starburst Galaxies IC4686/4687

J, H, Ks

J, H, Ks+Paschen- α



SWIMS Dewar Layout




MOS
Slit Plate





SWIMS Optics

(Design/Fabrication : Optcraft)

- * Split collimated beam using a Dichroic Mirror(DM) at 1.4mm
- * Final F-ratio=4.8 : 0.13"/pix
- * Independent filter wheels for NBFs to avoid wavelength offset
- * Each focal plane is covered by 2 H2RGs




→
Future






SWIMS on Subaru/Cassegrain




- * TAO 6.5m not available before 2016
- * First science with Subaru
- * Collimator design optimized for Subaru
(Re-optimized to TAO by changing the collimator unit)
- * FoV of 6.6' x 3.3' (MOIRCS : 7'x4')
- * 0.10"/pix



Performance of Optics (Subaru Design)



Blue Channel




Red Channel







Focal Plane Arrays

- * 8 HAWAII2 RGs / $2.5\mu\text{m}$ cutoff
=> Currently only 4 procured/delivered
- * SIDE CAR ASICs for readout
- * Covers central $6.6' \times 3.3'$ FoV@Subaru
- * $0.1''/\text{pix}$ sampling



Dark Current $< 0.005\text{e-}/\text{s}$







MOS Slit Plate Exchanger


(Design/Fabrication : Sentencia)

- * Based on the design of MOIRCS
 - * Turret-type mask stocker
 - * Robotic mask exchanger






MOS Slit Unit / Holder



- * Maximum # of mask slit : 20
- * New design with high reliability
 - * Magnet – latch (Both at the focus and the stock)
 - * Operative even at the TAO Nasmyth focus
 - * Curved mask to adjust focal plane curvature



Prototype Mask Holder





Schedule



- * 2010/Nov : Array #1, #2 delivery
- * 2011/Jan : Closing design phase
- * 2011/Jan : Array #3, #4 delivery
- * 2011/Jan : Dichroic mirror delivery
- * 2011/Mar : Completion of a new laboratory building
- * 2011/Mar: Delivery of the dewar, MOS, optics components
- * 2011/Q2-2012/Q2 : Assembly, adjustment, etc...
- * 2012/Q3 or later : Transport to Subaru, setup
- * 2013/Q1 : First Light at Subaru ?





New Building at Mitaka

* Will be completed in mid-March








Mask Catcher Unit





Atmospheric Transmittance





Dichroic Mirror